BRUHAT BANGALORE MAHANAGARA PALIKE

No: EE(SJN)/e-Proc/QTN/06/2025-26

Office of the Executive Engineer
Shivajinagara Division,
Thimmaiah Road, Queens Road
Bangalore - 560001
Date: 01-07-2025

Short Term Quotation Notification For Rates

The Quotation are invited by the undersigned on behalf of the Chief Commissioner / Zonal Commissioner, BBMP from the Reputed agencies / Suppliers / Distributors / Contractor for the work of **Supply, Casting, Erection and Fixing of Dr B R Ambedkar Statue in Shivajinagara Division.** The Interested supplier / agencies are requested to Submit / Upload their quotation Through https://kppp.karnataka.gov.in/. on or before 10-07-2025 at 4:00 pm as details in the table indicated below, the quotation shall be opened on 11-07-2025 at 4:30 pm

Sl No	Particulars	Unit	Qty
01	Providing and fixing selected quality granite stone made barricade of size 150 mm and 250 mm in top & bottom diameter respectively upto 900 mm depth with 2 rows of chains spaced at 2 mtr interval of approved size and shape, including cutting, chisteling, dressing, grinding and finishing as per approved drawings and fixing with cement mortor 1:3 with cost of all materials, labour and HOM of machineries, loading, unloading, with all lead and lift, transportation etc., complete., confiming IS quality & pattern/design provided in complete manner as per specification and the direction of engineer incharge. (Quotation Rate Excluding GST)	Mtr	40.00
02	SITC of Works Contract of Custom Artist Designed Statue made of broze material featuring Dr.B R.Ambedkar in seated posture with constitution of India book in hand. The statue will be 6.5' tall (and proportionate width) with average thickness of 12 to 16 mm bronze sheet from ground which includes the pedestal at floor area. The unit will be mounted to floor area.. , including cost of all materials, making clay model, making mould, making fibre glass statue, making plaster of parris piece mould, making wax statue, bronze casting, welding of bronze statue in foundry, bracing with steel flats with nut & bolts for structural stability, transportation, hoisting	Unit	1.00

	parts on to pedestal, welding steel structure and bronze parts together,final finishing and painting, installation on pedestal at site i.e work spot, including all Artists,skilled and unskilled labour, hiring of machineries, transportation and all other incidental charges for successful completion of work in coordination with civil works, includes the certificates to be obtained from the Quality assurance authorities etc. complete as per the directions of Engineer-in-charge of work. (Quotation Rate Excluding GST)		
03	SITC of Works Contract of Custom Artist Designed Anamorphic Perspective Metal Art Installation featuring the appearance of Dr. Ambedkar's face to be formed when viewed from specific vantage point or viewing area. When viewed from generic angle will look like a line of vertical louvers with abstarct shapes at different points of the vertical louvers. The entire art installation will be made of vertical MS Square pipes 2" x 2" with necessary base, top covering treatment, anchoring to floor base plate and the abstract shapes to be made of MS metal 3mm thick MS metal sheet. The metal pipe and abstract shapes as per perspective design will be firmly embedded on the each of the vertical pipe. The entire art installation will be 10'w x 10' h. Thee MS metal units will be treated for anti-corrosion and powder coated / painted in black colour as per the design. The floor area of the installation surface will feature metal base plate 10mm thick rectanglar in shape (basedon CG load)which will hold the array of the vertical louvers approx 24 nos. The base plate will be mounted to the floor area with required nuts and bolts. The installation is to viewed from a minimum distance of 50' away from the art installation to see the abstract shapes forming into the face of Dr. Ambedkar the rate quoted is including cost of all materials, transportation, hoisting parts, welding steel structure, final finishing and painting, installation at work spot, including all Artists, skilled and unskilled labour, hiring of machineries, transportation and all other incidental charges for successful completion of work in coordination with civil works, includes the certificates to be obtained from the Quality assurance authorities etc. complete as per the directions of Engineer-in-charge of work. (Quotation Rate Excluding GST)	Unit	1.00
04	SITC of Works Contract of Custom Artist Designed Preamble of Constitution of India will be made larger than life size measuring 10' x 15' and will be mounted on the custom created backwall which will feature in 2 different languages - Content Styling, designing in English and Kannada. The Ornamental boundary design along four sides of the constitution of India will be custom designed and fabricated in 2mm MS Metal Sheet, laser engraved / cut as per design and will glow from behind to give a glow effect in the evening based on the ligthting design and fixtures mentioned in the lighting works. The metal will be treated for anti-corrosion and suitable paint treatment as per the final approved design. Both the language art works will be mounted on the wall area	Unit	2.00

	behind the site border facing the traffic junction signal. The text and font will be designed suitable for reading from a minimum distance of 15-20 feet from the wall. The unit will have frame structure designed to mount on to the wall and designed to accomodate lighting design from behind. Warranty 1 year. (Quotation Rate Excluding GST)		
05	DIGITAL TIMER - Automatic Digital Timer Switch DIN Rail Mounted Type, input 180-250V, internal battery to retain programming schedule even in case of power failure, Working Voltage: Ac220v/50hz /Working Temperature: - 20℃~ 60℃ / Switch Capacity: 16 Ampere / Programmable Number:16 Programs / Day / Timing Error :≤2 Seconds Per Day / Consumption PowerConsumption:≤5w / Battery Cell : Rechargeable Battery (Quotation Rate Excluding GST)	No	2.00
06	SITC of architectural lighting for Dr. Ambedkar Bronze statue (as per approved designs) Statue lighting to cover statue of 6.5' h x 2.5' wide sitting posture (golden colour), 15º/25º beam angles, 12-15W or as recommended, 3000K, IP65, mounting accessories for max safety. Colour: Grey / Black. Warranty 1 year.(Quotation Rate Excluding GST)	No	6.00
07	SITC of architectural lighting for installation white backwall (as perapproved designs) High quality 1 mtrs wide Wall Washers lights , Power: 100W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 45º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year.(Quotation Rate Excluding GST)	No	30.00
08	SITC of architectural lighting for installation white high backwall (as perapproved designs) High quality spot lights , Power: 15W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 15º/30º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST)	No	25.00
09	SITC of architectural lighting for Floor Area (as perapproved designs) High quality floor mounted spot lights , Power: 0.5W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 5º/10º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST)	No	25.00
10	PVC INSULATED MULTICORE WIRE - SITC of PVC insulated multicore electricalunarmored flexible 3C x 1.5 Sqmm powercablehaving less electrical losses. This PVC insulatedand round sheathed wire features a bright multistrands copper conductors and it supports voltage grade upto 1100V. (As per actuals depending upon the site condition) - polycab /finolex / havells / equivalent (Quotation Rate Excluding GST)	Set	1.00

11	IP65 T CONNECTORS - SITC of IP65 "T" power connectors easy andextremely precise locking system. High impactmaterials - long-lasting and reliable (Quotation Rate Excluding GST)	No	50.00
12	IP65 I CONNECTOR - SITC of IP65 "I" power connectors having 3/4pole cable connector, chuck type strain relief,Current rating 20Arms continuous, Easy andextremely precise locking system "Quick Lock" High impact materials - long-lasting and reliable (Quotation Rate Excluding GST)	No	50.00
13	ACCESSORIES & ONSITE DETAILING - SITC of additional accessories for installing the lights as per the final drawing/site condition consisting of clamps, brackets, angles, joints, bends, hardwares like fasterners, nut & bolts etc., (Quotation Rate Excluding GST)	Job	1.00
14	WATERPROOF POWER JUNCTION BOX - SITC of water proof power junction box/ powercable terminal box, IP65 made up of rugged, non-corrosive, high impact polycarbonate, molded nylon encases. connectors that use screw compression tosecure the wires, protection against water jets and dust from all directions, includes 5 Way min 10A connector terminal block Max. dimension :80x250x85mm(Quotation Rate Excluding GST)	No	10.00
15	THEAMATIC LIGHTING DESIGN SERVICES - Architectural Lighting design services for items mentioned in section B (Quotation Rate Excluding GST)	Job	1.00
16	IP65 DRIVERS 130W Water proof Drivers(Quotation Rate Excluding GST)	No	25.00
17	PACKAGING & HANDLING, LOGISTICS, SCAFOLDING, BOOM LIFT SERVICES, LABOUR SERVICES (Quotation Rate Excluding GST)	Job	1.00

Following shall be the calendar events of Tendering: to be read as:

1. Tender Document may be Downloaded from the KPPP Portal of From :03-07-2025, 16.00 Hours
2. Last Date for Uploading the filled Tender Document is 10-07-2025 16.00 Hours.
3. Date of Opening of the quotation is on 11-07-2025 04.30 hours if possible or next working day.

Terms and Conditions:

1. The Agency shall quote the rate as per the specification
2. The rate quoted shall be inclusive of all Material, labour, Fabrication, Transportation etc. (Excluding GST)
3. The quotations are invited for the purpose of budgetary offer for adopting rates in estimate.
4. The agencies do not have any claim for entrustment of work
5. Any other information shall be had from the office of the undersigned during office hours
6. BBMP reserves right to accept or reject the quotation part or all without

assigning any reason.

Sd/-
Executive Engineer
Shivajinagara Division

Copy Submitted to :

1. Honorable Administrator for kind information.
2. Honorable Chief Commissioner for kind information
3. Zonal Commissioner (East)/Special Commissioner (Projects) for kind information
4. Engineer – in – Chief for kind information
5. Chief Engineer (East) for kind information
6. CAO / Chief Auditor for kind information
7. I. T. Advisor with a Request to publish the same in the BBMP Website
8. Public Relation Officer, BBMP for information and to publish in two leading National Newspapers in Kannada and English Notice Board.
9. Office Copy

Executive Engineer
Shivajinagara Division